

D.A.V. PUBLIC SCHOOL, NAYATOLA, KESHOPUR, JAMALPUR, MUNGER, BIHAR.

PH:-06344-200051(O) ,MOB:-9430982996, E-MAIL-ID:-dav_jamalpur@rediffmail.com

REF:-DAV-JM/SB-1/PB/BOQ/01/20-21

Date:- 15 OCT.2020

BILL OF QUANTITIES

LAYING OF PAVER BLOCKS FOR D.A.V. PUBLIC SCHOOL, JAMALPUR, MUNGER, BIHAR.

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.	Rate	Amount
		(1) FIXING OF 80 MM THICK C.C. PAVER BLOCKS OF M-35 GRADE NEAR SHED				
		Area of pavers block = 1440 Sft. (133.83 Sqm)				
		SECTION- I (PAVERS WORK)				
1	11.79	Providing and laying factory made chamfered edge Cement Concrete paver blocks of required strength thickness & size/shape, made by table vibratory method, to attain superior smooth finish using PU or equivalent moulds, laid in required grey colour & pattern over 50mm thick compacted bed of coarse sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compacting by using plate vibrator, filling the joints with jamuna sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in footpath, parks, lawns, drive ways or light traffic parking etc. all complete as per manufacture's specifications & direction of Engineer-in charge.				
	11.79.1	(a) 80 mm thick c.c.paver blocks of M-35 grade with approved colour design and pattern.	66.915	Sqm		
	11.79.2	(a) 80 mm thick c.c.paver blocks of M-35 grade with white colour design and pattern.	66.915	Sqm		
		TOTAL				
		ROUNDUP				
		Cost of Pavers Block per Sft.				

D.A.V. PUBLIC SCHOOL, NAYATOLA, KESHOPUR, JAMALPUR, MUNGER, BIHAR.

PH:-06344-200051(O) ,MOB:-9430982996, E-MAIL-ID:-dav_jamalpur@rediffmail.com

REF:-DAV-JM/SB-1/PB/BOQ/01/20-21

Date:- 15 OCT.2020

FOR TECHNICAL APPROVAL

SAND FILLING BELOW PAVER BLOCKS FOR D.A.V. PUBLIC SCHOOL, JAMALPUR, MUNGER, BIHAR.						
Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.	Rate	Amount
		(2) SAND FILLING BELOW 80 MM THICK C.C. PAVER BLOCKS OF M-35 GRADE NEAR SHED				
		Sand filling below pavers block = 2880 Cft. (81.61 Cum)				
		SECTION- I (EARTH WORK)				
1	2.28	Supplying and filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete.	81.61	Cum		
		TOTAL				
		ROUNDUP				
		Cost of filling sand per Cft.				